


Republic of the Philippines

Department of Education





DepEd ORDER No. **21**, s. 2011 MAR 0 4 2011

GUIDELINES ON THE INSTITUTIONALIZATION OF "BAYANIHANG ESKWELA,"
AS A COMMUNITY-BASED PUBLIC-PRIVATE MONITORING OF PROJECTS
UNDER THE CY 2011 REGULAR SCHOOL BUILDING PROGRAM (RSBP)
AND IN AREAS EXPERIENCING ACUTE CLASSROOM
SHORTAGE (RED AND BLACK SCHOOLS)

To:

Regional Secretary, ARMM

Regional Directors

Schools Division/City Superintendents

Regional/Division Physical Facilities Coordinators

All Others Concerned

- 1. The Bayanihang Eskwela (BayEsk) is a recognized community-based public-private monitoring of school building projects being spearheaded by the Government-Watch (G-Watch) of the Ateneo School of Government which has forged partnerships with the Department of Education (DepEd), Department of Public Works and Highways (DPWH), Office of the Ombudsman (OMB), Girl Scouts of the Philippines (GSP) and the Boy Scouts of the Philippines (BSP).
- 2. A Memorandum of Agreement (MOA) was signed by the abovementioned stakeholders that launched the "Bayanihang Eskwela," which aimed at strengthening project monitoring and evaluation of government projects for the purpose of minimizing corruption and improving the effectiveness in the delivery of government services.
- 3. The third run of BayEsk will cover the monitoring of the implementation of projects under the Regular School Building Program (RSBP) and the areas experiencing acute classroom shortage (Red and Black Schools).
- 4. Enclosed is the signed MOA (Enclosure No. 1) and the implementing guidelines (Enclosure No. 2).

5. Immediate dissemination of this Memorandum is desired.

BR. ARMIN A. LUISTRO FSC

Secretary

Encls.: As stated Reference: None

To be indicated in the <u>Perpetual Index</u> under the following subjects:

PROGRAMS PROJECTS

RULES & REGULATIONS SCHOOL BUILDING

Madel/MCR:DM- <u>Guidelines Bayanihang Eskwela</u> 3-2-11/03-03-11



MEMORANDUM OF AGREEMENT

Annex A

KNOW ALL MEN BY THESE PRESENTS:

This Memorandum of Agreement (the "Agreement") entered into and executed by and between:

The DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS (DPWH), an institution duly organized and existing under the laws of the Republic of the Philippines, having its principal place of office at Bonifacio Drive, Port Area, Manila, represented by its Secretary, ROGELIO L. SINGSON., hereinafter referred to as the "DPWH";

The DEPARTMENT OF EDUCATION (DepED), an institution duly organized and existing under the laws of the Republic of the Philippines, having its principal place of office at Meralco Avenue, Pasig City, represented by its Secretary, BR. ARMIN A. LUISTRO FSC, hereinafter referred to as the "DepED";

The OFFICE OF THE OMBUDSMAN (OMB), an institution duly organized and existing under the laws of the Republic of the Philippines, having its principal place of office at Agham Road, North Triangle, Diliman, Quezon City, represented by the Ombudsman, MA. MERCEDITAS N. GUTIERREZ, hereinafter referred to as the "OMB";

The ATENEO SCHOOL OF GOVERNMENT, with principal office at Room 406, Ateneo Professional Schools, Rockwell Center, Makati City, represented by the Dean, DR. ANTONIO G. M. LA VIÑA, hereinafter referred to as the "ASoG";

The BOY SCOUTS OF THE PHILIPPINES, with principal office at 181 Natividad Almeda-Lopez St., Ermita, Manila, represented by the Secretary General, MR. JOSE RIZAL C. PANGILINAN, hereinafter referred to as the "BSP":

-and-

The GIRL SCOUTS OF THE PHILIPPINES, with principal office at 901 Padre Faura St., Ermita, Manila, represented by the National Executive Director, MA. DOLORES T. SANTIAGO, hereinafter referred to as the "GSP":

WITNESSETH: That:

WHEREAS, all parties officially recognize the *Bayanihang Eskwela* project as a community-based public-private monitoring of school building projects;

AS

Japan Japan

K

1

Algh

W.

h huur 1 hy

WHEREAS, all parties have underscored the importance of strengthening project monitoring and evaluation systems of government agencies for the purpose of minimizing corruption and improve the effectiveness in the delivery of government services;

WHEREAS, all parties involved recognize the role of civil society organizations (CSOs) in helping the government reduce corruption and raise the quality of governance in the country;

WHEREAS, the first and second rounds of Bayanihang Eskwela enabled the testing of tools that allowed certain communities in Luzon, Visayas and Mindanao to participate in the monitoring of school-building projects;

WHEREAS, the third round aims to institutionalize the gains of Bayanihang Eskwela by institutionalizing a mechanism for civil society participation in the monitoring of the Regular School Building Program (RSBP) and the Red and Black School Building Program implementation using the tools and selected processes of Bayanihang Eskwela.

WHEREAS, the third round shall also include a policy study that would assess the impact of government's SBP allocation policies in addressing the country's problem on acute classroom shortage.

NOW, THEREFORE, for and in consideration of the above premises, all parties agree on the following terms and conditions as follows:

1.0 Responsibilities of the Parties

1.1 The DPWH shall---

- assign the Task Force for School-Building Projects to coordinate with the CSOs for the Bayanihang Eskwela project;
- 1.1.2 inform the Regional and District offices about the project and the involvement in the project of other key government agencies and CSOs through a Memorandum Order from the Secretary;
- provide the CSOs all documents, such as contract and program 1.1.2 of work, and all information relevant to the implementation of school building construction projects covered in the project;
- 1.1.3 provide CSO participants an orientation-seminar on the DPWH systems and procedures on the monitoring and inspection of school building projects:
- co-organize with G-Watch the conduct of the Briefing-Orientation on the conduct of the Bayanihang Eskwela project and instruct District Engineers to attend said activity;
- receive, respond to and act on feedback, comments and recommendations made by the CSOs regarding implementation and outcome of the project;

assist in the conduct of the Bayanihang Eskwela policy study on government school building allocation by providing pertinent documents and resource persons;

him 1 h

- 1.1.7 co-formulate with other stakeholders an institutionalized mechanism for civil society participation in the monitoring of the Regular School Building Program (RSBP) and the Red and Black School Building Program implementation using the tools and selected processes of Bayanihang Eskwela, and
- 1.1.8 give inputs to the easy-to-use Bayanihang Eskwela manual that would lay down how to conduct a community-based monitoring of SBPs and facilitate the implementation of the institutionalized mechanism to be formulated.

1.2. The DepED shall---

- 1.2.1 assign the Physical Facilities and Schools Engineering Division (PFSED) to coordinate with the CSOs for the *Bayanihang Eskwela* project;
- 1.2.2 inform the Regional and Division offices about the project and the involvement of other key government agencies and CSOs through a Memorandum Order from the Secretary;
- 1.2.3 provide the CSOs all documents, such as contract and program of work, and all information relevant to the implementation of school building construction projects covered in the project;
- 1.2.4 provide CSO participants an orientation-seminar on the DepED systems and procedures on the monitoring and inspection of school building projects;
- 1.2.5 co-organize with G-Watch the conduct of the Briefing-Orientation on the conduct of the *Bayanihang Eskwela* project and instruct School Principals to attend said activity;
- 1.2.6 send school representatives to the monitoring and inspection activities of the *Bayanihang Eskwela* project;
- 1.2.7 receive, respond to and act on feedback, comments and recommendations made by the CSOs regarding the implementation and outcome of the project;
- 1.2.8 assist in the conduct of the *Bayanihang Eskwela* policy study on government school building allocation by providing pertinent documents and resource persons;
- 1.1.9 co-formulate with other stakeholders an institutionalized mechanism for civil society participation in the monitoring of the Regular School Building Program (RSBP) and the Red and Black School Building Program implementation using the tools and selected processes of Bayanihang Eskwela, and
- 1.1.2 give inputs to the easy-to-use Bayanihang Eskwela manual that would lay down how to conduct a community-based monitoring of SBPs and facilitate the implementation of the institutionalized mechanism to be formulated.

thum 1 hy

12/2

Jam - il

7

Vocability A

Jh-

1.3 The Ombudsman shall---

- 1.3.1 assign the Bureau of Resident Ombudsmen as liaison to the *Bayanihang Eskwela* project;
- 1.3.2 send, whenever practicable, representatives to the actual monitoring and inspection of school building projects;
- 1.3.3 receive, respond to and act on reports of anomalies, irregularities and corruption uncovered in the monitoring and inspection activities of the project.

1.4 The Ateneo School of Government shall---

- 1.4.1 assign the G-Watch Project Team as the central coordination unit for the CSO participation in the *Bayanihang Eskwela* project;
- 1.4.2 coordinate with the assigned liaison offices of the government for the project;
- 1.4.3 coordinate the activities of CSOs participating in the project;
- 1.4.4 prepare all the reference materials to be used by the CSOs in the monitoring and inspection activities;
- 1.4.5 facilitate the transmission of all materials and information to the participating CSOs;
- 1.4.6 ensure the proper conduct of the participating CSOs by defining their duties and responsibilities;
- 1.4.7 report feedback, comments and recommendations to DPWH, DepEd, Office of the Ombudsman and other participating government agencies, regarding the implementation and outcome of the monitoring and inspection activities;
- 1.4.8 conduct a policy study on government school building allocation under the Bayanihang Eskwela project;
- 1.1.3 co-formulate with other stakeholders an institutionalized mechanism for civil society participation in the monitoring of the Regular School Building Program (RSBP) and the Red and Black School Building Program implementation using the tools and selected processes of Bayanihang Eskwela, and
- 1.4.9 draft an easy-to-use Bayanihang Eskwela manual that would lay down how to conduct a community-based monitoring of SBPs and facilitate the implementation of the institutionalized mechanism to be formulated.

1.5 The Boy Scouts of the Philippines and the Girl Scouts of the Philippines shall---

Frame -2

9

W

A The

thomas hy

h

- 1.5.1 take the lead in the mobilization of CSO monitors and inspectors for the *Bayanihang Eskwela* project;
- 1.5.2 facilitate and coordinate the participation of Parent-Teacher-Community Associations (PTCAs) and other local groups in the project;
- 1.5.3 send participants to the Briefing-Orientation for the Bayanihang Eskwela project;
- 1.5.4 send feedback, comments and recommendations to G-Watch regarding the implementation and outcome of the monitoring and inspection activities.
- 1.1.4 co-formulate with other stakeholders an institutionalized mechanism for civil society participation in the monitoring of the Regular School Building Program (RSBP) and the Red and Black School Building Program implementation using the tools and selected processes of Bayanihang Eskwela, and
- 1.5.5 give inputs to the easy-to-use Bayanihang Eskwela manual that would lay down how to conduct a community-based monitoring of SBPs and facilitate the implementation of the institutionalized mechanism to be formulated.
- 2.0 Non-Waiver The failure of either party to enforce any provision of this Agreement shall not be construed as a waiver or limitation of that party's right to subsequently enforce and compel strict compliance with every provision of this Agreement.
- **3.0** Severability If any provision of this Agreement shall be held to be invalid or unenforceable for any reason, the remaining provisions shall continue to be valid and enforceable.
- **Amendment** This Agreement shall not be altered, changed, supplemented or amended except by written instrument signed by the parties hereto.
- **5.0 Assignment** No party may assign any right or obligation under this Agreement, or any contract supplementary hereto, to a third party, without the prior written consent of the other parties. The provisions of this Agreement shall be binding upon and accrue to the benefit of the parties hereto and their respective successors and assigns.
- **Confidentiality** The parties shall not, prior to the evaluation, publicly disclose the findings of the project monitoring and inspection.

7.0 Governing Law - This Agreement shall be construed under and governed by the laws of the Republic of the Philippines.

748

5

M

4

The

8.0 Agreement Effectivity - This Agreement shall take effect upon the date of execution and shall remain in full force and effect for a period of twelve months (12) months, unless extended by mutual consent of the parties.



IN WITNESS WHEREOF, the parties have executed this Agreement as of the date and in the place written in the acknowledgment.

ROGELIO L. SINGSON

Secretary

Department of Public Works and Highways

BR. ARMIN A. LUISTRO FSC

Secretary

Department of Education

MA. MERCEDITAS N. GI TIERREZ

Ombudsman

JOSE RIZAL C. PANGILINAN

Secretary General

Boy Scouts of the Philippines

ANTONIO G. M. LA VIÑA, JSD

Dean

Ateneo School of Government

National Executive Director Girl Scouts of the Philippines

SIGNED IN THE PRESENCE OF:

AO, CESO V

sistant Secretary

Department of Public Works and

Highways

JOY G. ACERON

Director, G-Watch

Ateneo School of Govenrment

Resident Ombudsman

OLIVER R. HEBMANDEZ

OIC Director, Administrative Service Chief, Physical Facilities and Schools

Engineering Division - OPS

ACKNOWLEDGMENT

CITY OF	LIPPINES)) S.S.	
BEFORE ME. a // (V - (V) VO!V) (date)	Notary Public for and in th_, personally appeared:	ne above jurisdiction, this
Name	Government ID Reference Number	Date and Place Issued
Rogelio L. Singson	PASSPORT # : XX0626176	FEB. 49,2008
Br. Armin A. Luistro FSC	PASSPORT #: DPOOU7134	SEPT. 03, 2010
Ma. Merceditas N. Gutierrez	CCT #: 2009 183 571 18	JAN. 13, 2010, CITY OF QUEZON
Antonio G. M. La Viña, JSD	CTC #: 256 69353	JAN-12, 2010 , CITY OF MANILA
Jose Rizal C. Pangilinan	555 #: 33 - 409 5755 - 1	
Ma. Dolores T. Santiago	PASSPORT #: XX 5345 214	JAN: 23, 2010

all known to me and to me known to be the same persons who executed the foregoing instrument and who acknowledged to me that the same is their free and voluntary act and deed.

This instrument refers to a MEMORANDUM OF AGREEMENT which consists of six (6) pages, including the page whereon this acknowledgment is written and which is signed by the party and his instrumental witnesses on each and every page thereof.

WITNESS MY HAND AND SEAL on the date and at the place first written above.

Doc. No. 3 ; Page No. 62 ; Book No. 3 ;

Series 2010.

AISUM /S. GARLE HOYARY PHRLIC PTR. 3228825 1/2/10 & c IBP 207/58 1/ / 0 M & OB CPOLL 522/15 (2.)

By

AFF

7



REPUBLIC OF THE PHILIPPINES **DEPARTMENT OF EDUCATION**

Division of _______

	(Name of Scho	0)	
	PUNCHLIST OF CORRECTIVE WO	RKS / INSPECTION R Regular S	
Project School Location Region			
Contractor	: Initial Inspection Date:	Final Ins	pection
Item of Work	Description of Corrective Works	Remarks / Date Rectified	Signature of Engineer
		Note: The contractor agrees to import of the defect indicated in the above inspect to all the defect of the defect	ction report within
Jointly inspec	ted by:		
Cor	ntractor's Representative	Division Physical Faci	lities Coordinator
S Observer:	School Head/Principal	DepED Project (for Red and B	
Bayaniha	ang Eskwela SBP Coordinator	DPWH Project (for Regula	

MONITORING PROFILE						
Name of School: Location: District:				^	lame of Monitor:	
Division:					Organization:	
Project: Contractor: Planned Duration: Planned Cost:					ex: ge:	
GENERAL SCHOOL PROFILE						
General School Needs		Edu	ucation	al Developr	nent Indicators	_
Student Population	-			T Score	Year before Last SY:	
Teacher-student Ratio					Last SY:	
Textbook-student Ratio		L			This SY:	
Math		Cor	npletion	Rate	Year before Last SY:	
Science					Last SY:	l
English		<u> </u>		4 -	This SY: Year before Last SY:	
Filipino		Dro	pout Ra	ite	Last SY:	
Classroom-student Ratio					This SY:	1
Seat-student Ratio		L			71113 0 1 .	
Blackboard-Classroom Ratio						
			_			
PRE-CONSTRUCTION STAGE						
Monitoring Points		Yes	No		Details	
Activity 1: Site Identification						
1. Did the issue of "property ownership" surface	ce in the			Type of Pro		
project site identification?		j		□ public pro	operty orivate property	
Lumitaw ba sa site identification ang usapin s	a				ted private property	
pagmamay-ari ng lupa?				<u> </u>	<u> </u>	
2. Was the site suitable for the project? Angkop ba ang lugar sa proyekto?					ical concern ental concern	
Angkop ba ang lugar sa proyekto:				□ social cor	ncern	
3. Was there a meeting to discuss issues and				When:		
Nagkaroon ba ng pulong upang pag-usapan a	ing mga			Where:	d offices/groups:	
isyu?	-	ļ		Represente	d offices/groups:	
				□ DepED	D NGO	
		ļ		□ LGU	□ DENR	

Bayanihang Eskwela Checklist

Activity 2: Project Meeting

project site?

1. Was there a meeting to finalize project site?

2. Was the project management team formed? Binuo na ba ang project management team?

3. Was the documentation of property ownership in

Nagkaroon ba ng pulong upang pagdesisyunan ang

□ Barangay Office

□ Barangay Office Name of Project Head:

Type of Documentation

Represented offices/groups:

□ DPWH □ PTCA

□ NGO

DENR

When: Where:

> □ DPWH □ DepED

□ LGU

order? Maayos ba ang dokumentasyon ng pagmamay-ari ng lupa?	□ Deed of Donation □ Sale Document □ Annotated Original / Transfer Certificate of
	Title
Activity 3: Pre-Engineering Survey	
Was a pre-engineering survey conducted? Nagsagawa ba ng pre-engineering survey?	When: Lead in the survey: Observations:
Did the survey confirm that the building to be constructed fit the land area? Nakumpirma ba ng survey na kasya ang itatayong gusali sa napiling lugar?	Area needed: Area available:
Activity 4: Preparation of the Program of Works	
Were you given a copy of the Program of Works?	Cost:
Binigyan ka ba ng kopya ng Program of Works?	Duration:
Did you have difficulty getting a copy of the Program of Works? Nahirapan ka bang himingi ng kopya ng Program of Works? Works?	Elaborate:
Is the Program of Works consistent with DepED standards? Ang Program of Works ba ay naaayon sa itinakdang	DepED standards: cemented floor smooth finished walls painted walls, ceiling and roofing
pamantayan ng DepED?	□ full cathedral-type ceiling (for single-storey) or drop ceiling (for multi-storey) □ complete set of windows (2 facing walls) □ two entrances with doors □ complete electrical wires and fixtures □ roofing or weather protection □ blackboard
Activity 5: Site Inspection	
Was a site inspection conducted?	When:
Nagsagawa ba ng site inspection?	Where: Represented offices/groups: DPWH DTCA DepED NGO LGU DENR Barangay Office
2. Did DPWH give orientation on project plans during site	When:
inspection? Nagsagawa ba ng project orientation?	
3. Was the information given in the orientation consistent with the Program of Works? Ang impormasyon bang ibinigay sa orientation ay naaayon sa nakasaad sa Program of Works?	Inconsistencies (if any):
Activity 6: Bidding	
Was bidding conducted for the project?	l If yes,
Nagsagawa ba ng bidding para sa proyekto?	When: Where: Who presided:
	If no, Mode of procurement used:
	Amount of Contract: Name of Contractor:
Were there issues and concerns raised?	Elaborate:
May mga usapin bang tinalakay?	
3. Was post-qualification conducted?	Lowest Calculated Responsive Bids:

Nagsagawa ba ng post-qualification?	1. 2. 3
4. Did you do your own checking of contractor's capacity? Nagsagawa ka ba ng sariling pagsisiyasat sa kapasidad ng contractor?	Findings:
5. Was the Notice to Award sent to the winning bidder? Naipadala ba ang Notice of Award sa nanalong bidder?	When:
6. Did the winning bidder send Letter of Acceptance? Nagbigay ba ng Letter of Acceptance ang nanalong bidder?	When:
7. Was the Notice to Proceed sent to the winning bidder? Naipadala ba ang Notice to Proceed sa nanalong bidder?	When:

CONSTRUCTION STAGE

Monitoring Points	Yes	No	Details
Activity 1: Earthworks and Excavation	<u>. </u>	L	
1. Were garbage, plants, remains of old structures, and other obstructions removed and disposed of properly? Maayos bang tinanggal at itinapon ang mga basura, halaman, tira ng lumang istruktura at iba pang sagabal sa konstruksyon?			Observations:
2. Were there items (e.g. structures, trees) that had been unnecessarily damaged? Mayroon bang bagay, istruktura o puno na aksidenteng nasira?			What: Who is responsible for the damage?
3. Was the excavation area in accordance with the plan in the Program of Works? Ang sukat ba ng excavation ay ayon sa plano sa Program of Works?			Planned Area in Program of Works: Actual Excavated Area:
Did the excavation disturb any slopes? May nasira bang talilis dahil sa paghuhukay?			Observations:
5. Was the excavated surface smooth and uniform? Patag at pantay ba ang ibabaw ng hukay?			Observations:
6. Were the excavated materials disposed of properly? Itinapon ba nang maayos ang mga nahukay?			Observations:
7. Were the excess materials (e.g. rocks and boulders) used as backfill materials? Ginamit bang backfill materials ang mga bato?			If yes, was there permission from the Project Engineer?
Activity 2: Concrete Works			
Was Type A or Portland Cement used? Type A o Portland Cement ba ang ginamit?			
2. Were the bags of cement stored properly? Nakaimbak ba nang maayos ang mga bag ng semento?			Indicators: □ Bags of cement may get wet in the storage room □ Storage room has cracks or openings between walls and roofs □ Flooring is above ground □ Cement bags are stacked close together
0.104			Observations:
Were cements that already solidified or which contain lumps of caked cement still being used? Ginagamit pa rin ba ang mga sementong namuo-muo at			Observations:

nagkatipak-tipak na?	
4. Were cements salvaged from discarded or used bags still	Observations:
being used?	
Ginagamit pa rin ba ang mga tira-tirang semento? 5. Did they mix cement with clean water?	Indicators:
Malinis na tubig ba ang hinahalo sa semento?	□ no oil / no slat / no acid / no álcali / no
Mailins ha lubig ba ang hinahalo sa semento?	grass
	3 ,
	Observations:
Were quality coarse aggregates (gravel) used?	Indicators:
Tamang kalidad ba ang ginagamit na graba?	□ Color is blue, not brown / Clean, no mixture of soil or clay / Hard, strong and
	durable; do not break easily / Free from any
	adherent coatings or crystals
	,
	Observations:
7. Were quality fine aggregates (sands) used?	Indicators:
Tamang kalidad ba ang ginagamit na buhangin?	□ Must come from the river, not sea (color: black) / Sands from different sources are not
	combined together
	Combined together
	Observations:
8. Was the correct proportion of water, cement and	Indicators:
aggregates followed in the construction of columns and	□ Water: 15%-20% / Cement: 7%-14% /
beams?	Aggregates: 66%-78%
Sinusunod ba ang tamang panumbasan sa paghahalo ng	Observations:
tubig, semento at aggregates?	
9. Were the materials in good shape?	Indicators: □ no rust / no cracks and laminations / no
Nasa maayos na kondisyon ba ang mga materyales?	surface irregularities or mill scale
	Surass in egalaniles of this seals
	Observations:
10. Were the type, size and quantity of materials in	Type Size Qty
accordance with the Program of Works?	
Ayon ba sa Program of Works ang uri, sukat at bilang ng	
materyales?	
11. Were the materials stored properly?	Indicators:
	□ Placed on a platform or above ground
11. Were the materials stored properly?	
11. Were the materials stored properly?	□ Placed on a platform or above ground
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry	☐ Placed on a platform or above ground☐ It does not pose danger or injury to people☐ Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works?	☐ Placed on a platform or above ground☐ It does not pose danger or injury to people☐ Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng wires?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Actual:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng wires? Activity 4: Carpentry	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng wires? Activity 4: Carpentry 1. Did the contractor buy and deliver the materials needed?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng wires? Activity 4: Carpentry 1. Did the contractor buy and deliver the materials needed? Ang contractor ba ang bumili at naghatid ng mga materyales?	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Observations: Observations:
11. Were the materials stored properly? Maayos ba ang pag-iimbak sa mga materyales? Activity 3: Masonry 1. Was the size of hollow blocks used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng hollow blocks? 2. Was the size of steel bars used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng steel bars? 3. Was the size of wires used in accordance with the Program of Works? Ayon ba sa Program of Works ang sukat ng wires? Activity 4: Carpentry 1. Did the contractor buy and deliver the materials needed? Ang contractor ba ang bumili at naghatid ng mga materyales? 2. Did the contractor buy the right number, size, and shape of	□ Placed on a platform or above ground □ It does not pose danger or injury to people Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Program of Works: Actual: Observations: Observations: Observations:

Were the timber materials in good condition? Ang mga kahoy ba ay nasa maayos na kondisyon?	Indicators: □ no loose knots / no split / no worm hole / no decay / no warp / no ring separation
Were the materials stored properly?	
Maayos ba ang pagkaimbak ng mga materyales?	
Activity 5: Painting	
Was the paint of good quality? Maayos ba ang kalidad ng pintura?	Indicators: □ no excessive setting / no curdling / no caking / no gelling or thickening / no color separation / no lumps and skins Observations:
2. Did the paint brush easily? Madali bang lumapat ang pintura?	Indicators: unith good levelling properties / no running or sagging when applied to smooth vertical surface Observations:

POST-CONSTRUCTION STAGE

Monitoring Points	Yes	No	Details
Process	1		
Was the School Principal consulted on the Plans and Program of Works? Kinunsulta ba ang School Principal sa plano at Program of Works?			
Did DPWH District Engineering Office provide copy of Program of Works prior to construction?			
Nagbigay ba ng kopya ng Program of Works bago magsimula ang konstruksyon?			
Was the schedule announced prior to construction? Ipinaalam ba ang schedule bago magsimula ang konstruksyon?			When:
Was construction completed within schedule?			Start:
Natapos ba ang konstruksyon ayon sa schedule?			End:
Was a joint Final Inspection conducted?			When:
Nagsagawa ba ng joint Final Inspection?			Inspection Team members: DPWH DepED Barangay PTCA
Were defective works rectified within 15 days? Naayos ba ang mga maling trabaho sa loob ng 15 araw?			Defects rectified:
reaction and making transmit out tooking to draw:			2.
Was construction completed according to specifications?			Lacking:
Natapos ba ang konstruksyon ayon sa mga takdang specifications?		·	1.
, , , , , , , , , , , , , , , , , , ,			2.
			3.

Monitoring Points	(-)	(+)	Comments / Observations
Structure		1	
Concreting Wall & Column Footings Tie Beams/Beams Floor Slab Columns			
Roofing & Accessories Trusses/Rafters Purlins			

Corrugated GI Sheet			
Teckscrew	_		
Doors and Windows			_
Panel Doors			
Flush Doors			
Steel Doors	1		
Steel Casement Windows	- { - {		
Jalousie Windows			
Plumbing Works			
Pipes	1 1		
Fittings			
Fixtures			
Painting Works			
Roofings	1 1		
Interior & Exterior Walls			
Ceiling	1		
Doors & Windows			
Electrical Fixtures			
Rough-ins			
Wires			
Fixtures			
Bulbs/Fluorescents			

CONDUCIVENESS TO LEARNING

Monitoring Points	YES	NO	Comments / Observations
Indicators	·	ł	
Ventilation: Are the classrooms wellventilated? Maaliwalas ba ang loob ng mga			
silid-aralan?	_		
Lighting: Are the classrooms sufficiently lighted? Sapat ba ang liwanag sa loob ng mga silid-aralan?			
Space: Are the classrooms spacious enough for the students? Sapat ba ang lawak ng mga silidaralan para sa mga estudyante?			
Sanitation: Was the school building site sanitary?			
Malinis ba ang pinagtayuan ng mga silid-aralan?			What are the threats?
			How are they addressed?
Is the school building free from health threats?			
Ang mga silid-aralan ba ay walang banta sa kalusugan?			
Safety: Does the school building have safety features?			Emergency exit Security Grills Ramp

Bayanihang Eskwela Checklist		6 of 7

Mayroon bang safety features ang silid-aralan?	
Were there safety risks in the construction of the SBP? Nagkaroon ba ng mga banta sa kaligtasan noong itinatayo ang mga silid-aralan?	
Others: What other aspects of the school	Commendable:
building is either commendable or should still be improved?	Still needs improvements:
Ano pang aspeto ng silid-aralan ang kapuri-puri o kaya naman ay	Cam riceds improvements.
dapat pa ipagbuti?	
RESPONSIVENESS TO SCHOOL	NEED

Monitoring Points	YES	NO	Comments / Observations
Is the school under the Red and Black Category (Red – Equal to or more than 56 students per classroom; Black – No classroom available)? Nasa Red and Black Category ba ang eskwelahan, na nangangahulugang nasa 56 o higit pa ang estudyante kada silidaralan o kaya ay walang silidaralan sa eskwelahan?			Number of Classrooms: Number of Makeshift Classrooms: Number of Condemnable Classrooms: Number of Buildings: Number of Condemnable Buildings:
Is the design of the classroom appropriate for the school environment? Naangkop ba ang disenyo ng silidaralan sa kapaligiran ng eskwelahan? Is the design of the classroom appropriate for the community's culture?			

IMMEDIATE CONCERNS OF THE SCHOOL

Others: What are the school's immediate concerns? Ano pa ang ibang mahahalagang pangangailangan ng eskwelahan?	

ANNEX 3: The Bayanihang Eskwela Processing Template

The Bayanihang Eskwela Processing Template

The **Bayanihang Eskwela Processing Template** is used to consolidate the results of your monitoring with the use of your Bayanihang Eskwela checklist. Tally the results of your team's checklist using the tables below. Read the instruction carefully for each part, and answer according to what is asked for.

me of School:	Name of Monitors:
eation:	
trict:	
rision:	
oject:	
ntractor:	
nned Duration:	
nned Cost:	TOTAL # of Monitors:

The first part of the checklist on the general school needs will ask you to assess whether the school is faring well or not in the identified items. Fill up the third column, and then assess whether there is a 'shortage', 'sufficient' pr a 'surplus' of the resources that your schools needs.

GENERAL SCHOOL NEEDS	Standard/ Ideal Number	Actual School Data	Observation (Shortage, Sufficient, Surplus)
Student Population			
Teacher-student Ratio	1:35		
Textbook-student Ratio			
Math	1:1		
Science	1:1		
English	1:1		
Filipino	1:1		
Classroom-student Ratio	1:45		
Seat-student Ratio	1:1		
Classroom- blackboard Ratio	1:1		

Fill out the second column where needed (i.e. this year's national average for completion and dropout rate). Insert your school's data in 3rd column, and then assess whether it is above or below average/ideal after comparing it to the data in the 2nd column and insert your observation in the 4th column. Lastly, on the 5th column, assess whether the figures are improving, declining, or if remains stagnant.

Educational Development Indicators	ldeal/Average Number	Actual School Data	Observation Against Ideal Number	Improving, Stagnant, or Declining
School NAT Score	75 % (Passing Grade)	Year before Last SY: Last SY: This SY:		
Completion Rate	National Average Year before Last SY: Last SY: This SY:	Year before Last SY: Last SY: This SY:		
Dropout Rate	National Average Year before Last SY: Last SY: This SY:	Year before Last SY: Last SY: This SY:		

PRE-CONSTRUCTION STAGE

Monitoring Points	# of Yes	# of No	Explanation of Deviation
Activity 1: Site Identification		<u> </u>	
Did the issue of "property ownership" surface in the project site identification?			
Lumitaw ba sa site identification ang usapin sa pagmamay-ari ng lupa?			
Was the site suitable for the project? Angkop ba ang lugar sa proyekto?			
3. Was there a meeting to discuss issues and concerns?			
Nagkaroon ba ng pulong upang pag-usapan ang mga isyu?			
Activity 2: Project Meeting	1!		
1. Was there a meeting to finalize project site?			
Nagkaroon ba ng pulong upang pagdesisyunan ang project site?			
Was the project management team formed? Binuo na ba ang project management team?			
Was the documentation of property ownership in order?			

Maayos ba ang dokumentasyon ng pagmamay-ari ng	
lupa?	
Activity 3: Pre-Engineering Survey	
Was a pre-engineering survey conducted?	
Nagsagawa ba ng pre-engineering survey?	
2. Did the survey confirm that the building to be	
constructed fit the land area?	
Nakumpirma ba ng survey na kasya ang itatayong gusali	
sa napiling lugar?	
Activity 4: Preparation of the Program of Works	
Were you given a copy of the Program of Works?	
Binigyan ka ba ng kopya ng Program of Works?	
2. Did you have difficulty getting a copy of the Program of	
Works?	
Nahirapan ka bang himingi ng kopya ng Program of	
Works?	
Is the Program of Works consistent with DepED	
standards?	
Ang Program of Works ba ay naaayon sa itinakdang	
pamantayan ng DepED?	
Activity 5: Site Inspection	
Was a site inspection conducted?	
Nagsagawa ba ng site inspection?	
2. Did DPWH give orientation on project plans during site	
inspection?	
Nagsagawa ba ng project orientation?	
3. Was the information given in the orientation consistent	
with the Program of Works?	
Ang impormasyon bang ibinigay sa orientation ay	
naaayon sa nakasaad sa Program of Works?	
Activity 6: Bidding	
Was bidding conducted for the project?	
Nagsagawa ba ng bidding para sa proyekto?	
2. Were there issues and concerns raised?	
May mga usapin bang tinalakay?	
3. Was post-qualification conducted?	
Nagsagawa ba ng post-qualification?	
4. Did you do your own checking of contractor's capacity?	
Nagsagawa ka ba ng sariling pagsisiyasat sa kapasidad	
ng contractor?	
5. Was the Notice to Award sent to the winning bidder?	
Naipadala ba ang Notice of Award sa nanalong bidder?	
6. Did the winning bidder send Letter of Acceptance?	
Nagbigay ba ng Letter of Acceptance ang nanalong	
bidder?	
7. Was the Notice to Proceed sent to the winning bidder?	
Naipadala ba ang Notice to Proceed sa nanalong bidder?	

CONSTRUCTION STAGE

Monitoring Points	# of Yes	# of No	Details
Activity 1: Earthworks and Excavation			
1. Were garbage, plants, remains of old structures, and other			
obstructions removed and disposed of properly?			
Maayos bang tinanggal at itinapon ang mga basura,			
halaman, tira ng lumang istruktura at iba pang sagabal sa			
konstruksyon?			
2. Were there items (e.g. structures, trees) that had been			
unnecessarily damaged?			
Mayroon bang bagay, istruktura o puno na aksidenteng		İ	
nasira?			
3. Was the excavation area in accordance with the plan in the			
Program of Works?			
Ang sukat ba ng excavation ay ayon sa plano sa Program of			
Works?			
4. Did the excavation disturb any slopes?			
May nasira bang talilis dahil sa paghuhukay?			
5. Was the excavated surface smooth and uniform?			
Patag at pantay ba ang ibabaw ng hukay?			
6. Were the excavated materials disposed of properly?			
Itinapon ba nang maayos ang mga nahukay?			
7. Were the excess materials (e.g. rocks and boulders) used			
as backfill materials?			
Ginamit bang backfill materials ang mga bato?			
Activity 2: Concrete Works			
Was Type A or Portland Cement used?			
Type A o Portland Cement ba ang ginamit?			
Were the bags of cement stored properly?			
Nakaimbak ba nang maayos ang mga bag ng semento?			
Were cements that already solidified or which contain			
lumps of caked cement still being used?			
Ginagamit pa rin ba ang mga sementong namuo-muo at			
nagkatipak-tipak na?			
4. Were cements salvaged from discarded or used bags still			
being used?			
Ginagamit pa rin ba ang mga tira-tirang semento?			
5. Did they mix cement with clean water?			
Malinis na tubig ba ang hinahalo sa semento?			
6. Were quality coarse aggregates (gravel) used?			
Tamang kalidad ba ang ginagamit na graba?			
7. Were quality fine aggregates (sands) used?			
Tamang kalidad ba ang ginagamit na buhangin?			
Was the correct proportion of water, cement and			
aggregates followed in the construction of columns and	i		
beams?	i		
Sinusunod ba ang tamang panumbasan sa paghahalo ng	1		
tubig, semento at aggregates?			
9. Were the materials in good shape?	Ì	1	
Nasa maayos na kondisyon ba ang mga materyales?			
10. Were the type, size and quantity of materials in			
accordance with the Program of Works?	1		
Ayon ba sa Program of Works ang uri, sukat at bilang ng			
materyales?			
11. Were the materials stored properly?	Ì		
Maayos ba ang pag-iimbak sa mga materyales?			

Activity 3: Masonry	
1. Was the size of hollow blocks used in accordance with the	
Program of Works?	
Ayon ba sa Program of Works ang sukat ng hollow blocks?	
2. Was the size of steel bars used in accordance with the	
Program of Works?	
Ayon ba sa Program of Works ang sukat ng steel bars?	
3. Was the size of wires used in accordance with the Program	
of Works?	
Ayon ba sa Program of Works ang sukat ng wires?	
Activity 4: Carpentry	
Did the contractor buy and deliver the materials needed?	
Ang contractor ba ang bumili at naghatid ng mga materyales?	
2. Did the contractor buy the right number, size, and shape of	
materials as stated in the Program of Works?	
Ayon ba sa Program of Works ang bilang, sukat at hugis ng	
mga biniling materyales?	
Were the timber materials in good condition?	
Ang mga kahoy ba ay nasa maayos na kondisyon?	
4. Were the materials stored properly?	
Maayos ba ang pagkaimbak ng mga materyales?	
Activity 5: Painting	
1. Was the paint of good quality?	
Maayos ba ang kalidad ng pintura?	
2. Did the paint brush easily?	
Madali bang lumapat ang pintura?	

POST-CONSTRUCTION STAGE

Monitoring Points	# of Yes	# of No	Details
Process	J		
Was the School Principal consulted on the Plans and Program of Works? Kinunsulta ba ang School Principal sa plano at Program of Works?			
Did DPWH District Engineering Office provide copy of Program of Work prior to construction?			
Nagbigay ba ng kopya ng Program of Work bago magsimula ang konstruksyon?		_	
Was the schedule announced prior to construction?			
Ipinaalam ba ang schedule bago magsimula ang konstruksyon?			
Was construction completed within schedule?			
Natapos ba ang konstruksyon ayon sa schedule?		_	
Was a joint Final Inspection conducted?			
Nagsagawa ba ng joint Final Inspection?		i _	
Were defective works rectified within 15 days?			
Naayos ba ang mga maling trabaho sa loob ng 15 araw?			
Was construction completed according to specifications?			
Natapos ba ang konstruksyon ayon sa mga takdang specifications?			

Here in the "Structure" section of post-construction stage, the first column is also called "Monitoring Points". It contains the features to look for in a completed school building. The second and third columns contain the (+) and (-) signs, respectively. They must be checked accordingly depending on whether the feature is "present" or "absent" based on the requirements of the Program of Work. The fourth column asks you to answer whether the SBP is generally good, average or generally bad. Please aggregate your comments and observations as well.

Monitoring Points	# of	# of	Quality (Good/Average/Bad)
Monitoring Foilits	(-)	(+)	Quanty (Good/Average/Bad)
Structure			
Concreting Wall & Column Footings Tie Beams/Beams Floor Slab Columns			
Roofing & Accessories Trusses/Rafters Purlins Corrugated GI Sheet Teckscrew			
Doors and Windows Panel Doors Flush Doors Steel Doors Steel Casement Windows Jalousie Windows			
Plumbing Works Pipes Fittings Fixtures			
Painting Works Roofings Interior & Exterior Walls Ceiling Doors & Windows			
Electrical Fixtures Rough-ins Wires Fixtures Bulbs/Fluorescents			

CONDUCIVENESS TO LEARNING

For this part, follow the same instruction as in the Construction Stage: The first column contains the "Monitoring Points", which are in question-form answerable by "yes" or "no". For the second and third column, you will tally the number of 'Yes' and the number of 'No' that your monitors answered in their checklists. The fourth column asks for "Details" of the answer.

Monitoring Points	# of YES	# of NO	Comments / Observations
Indicators			
Ventilation: Are the classrooms well- ventilated? Maaliwalas ba ang loob ng mga silid-aralan?			

Lighting: Are the classrooms sufficiently lighted? Sapat ba ang liwanag sa loob ng mga silid-aralan?	
Space: Are the classrooms spacious enough for the students? Sapat ba ang lawak ng mga silidaralan para sa mga estudyante?	
Sanitation: Was the school building site sanitary? Malinis ba ang pinagtayuan ng mga silid-aralan?	
Is the school building free from health threats? Ang mga silid-aralan ba ay walang banta sa kalusugan?	
Safety: Does the school building have safety features? Mayroon bang safety features ang silid-aralan?	
Were there safety risks in the construction of the SBP? Nagkaroon ba ng mga banta sa kaligtasan noong itinatayo ang mga silid-aralan?	
Others: What other aspects of the school building is either commendable or should still be improved? Ano pang aspeto ng silid-aralan ang kapuri-puri o kaya naman ay dapat pa ipagbuti?	Commendable: Still needs improvements:

RESPONSIVENESS TO SCHOOL NEED

Monitoring Points	# of YES	# of NO	Comments / Observations
Is the school under the Red and Black Category (Red – Equal to or more than 56 students per classroom; Black – No classroom available)?			

Nasa Red and Black Category ba			
ang eskwelahan, na			
nangangahulugang nasa 56 o higit	<u> </u>		
pa ang estudyante kada silid-			
aralan o kaya ay walang silid-			
aralan sa eskwelahan?			
Is the design of the classroom			
appropriate for the school			
environment?			
Naangkop ba ang disenyo ng silid-			
aralan sa kapaligiran ng			
eskwelahan?			
Is the design of the classroom			
appropriate for the community's			
culture?			
Naangkop ba ang disenyo ng silid-			
aralan sa kultura ng komunidad?			

IMMEDIATE CONCERNS OF THE SCHOOL

Kindly list down the answers of your monitoring team members in the box below

Others: What are the school's immediate concerns? Ano pa ang ibang mahahalagang pangangailangan ng eskwelahan?	,
1 2	
3	

GENERAL FINDINGS

Using the data you have aggregated above, try to answer the questions below as faithfully as possible to what you have monitored. Explain briefly the reason for you answer

Variables	Planned/ Normative
Time	Was the implementation timely? Why?
Cost	Was it value for cost? Why?
Quantity	Was the quantity enough and did it follow standards?

Quality	Is it a quality School building? Why?	
Process	Were processes followed? Why or why not?	

GUIDELINES FOR THE INSTITUTIONALIZATION OF "BAYANIHANG ESKWELA" IN THE MONITORING OF PROJECTS UNDER THE CY 2011 REGULAR SCHOOL BUILDING PROGRAM (RSBP) AND IN AREAS EXPERIENCING ACUTE CLASSROOM SHORTAGE (RED & BLACK SCHOOLS)

A. Statement of Policy

- It is the policy of the Department of Education to promote Non-Government Organization's (NGO), private sector's and citizens' participation in the procurement process and contract implementation at all levels of the Department.
- 2. DepED also seeks to foster the spirit of volunteerism in the school building program of the government.
- The Department through the Physical Facilities and Schools Engineering Division (PFSED) envisions to provide quality services to its clientele by providing quality educational facilities.

B. Legal Bases

Article I, Section 3 of R.A. 9184 of the Government Procurement Reform Act (GPRA) states:

"All procurement of the national government, its departments, bureaus, offices and agencies, including state universities and colleges, government-owned and/or controlled corporations, government financial institutions and local government units shall, in all case, be governed by these principles:

- a. Transparency in the procurement process and in the implementation of procurement contracts;
- b. System of accountability where both the public officials directly or indirectly involved in the procurement process as well as in the implementation of procurement contract and the private parties that deal with government are, when warranted by circumstances, investigated and held liable for their actions relative thereto; and
- c. Public monitoring of the procurement process and the implementation of awarded contracts with the end in view of guaranteeing that these contracts are awarded pursuant to the provisions of this Act and its implementing rules and regulations, and all these contracts are performed strictly according to specifications".

Article V. Section 13 of R.A. 9184 or the Government Procurement Reform Act (GPRA) mandates all government agencies to invite private sector and NGO observers in all stages of the procurement process. It states:

"Sec. 13 Observers – To enhance the transparency of the process, the BAC shall, in <u>all stages of the procurement process</u>,

invite, in addition to the representative of the Commission on Audit, at least two (2) observers to sit in its proceedings, one (1) from a duly recognized private group in a sector or discipline relevant to the procurement at hand, and the other from a non-government organization: *Provided, however,* that they do not have any direct or indirect interest in the contract to be bid out. The observers should be duly registered with the Securities and Exchange Commission and should meet the criteria for observers as set forth in the IRR. (underscoring supplied.)"

Section D of DepED Order No. 59, s. 2007 entitled "Institutionalizing NGO and Private Sector Participation in the Department's Procurement Process" states that:

"Other than the stage/s of the procurement as spelled out in the IRR-A Sec. 13.3 of the R.A. 9184, private sectors, NGO representatives, and private citizens are to be invited as official and unofficial observers in the Contract Implementation and the Delivery and Acceptance stages."

The National Building Code and the Joint DepED-DPWH Memorandum: Guidelines for Coordination and Monitoring of DPWH Constructed School-buildings, 2008, and as amended in 2010, further elaborates the standard classroom/building designs and standard processes for the pre-to-post-construction stages of the government school building program.

C. Scope and Coverage

This policy will cover the implementation of the Regular School Building Program (RSBP) being implemented by the Department of Public Works and Highways (DPWH), and school building projects in areas experiencing acute classroom shortage (Red and Black Schools) being implemented by DepED.

D. Composition of the Community-Based SBP Monitoring Team

- The Community-Based SBP Monitoring Team shall consist of the following members:
 - School Head/Principal. The school head/principal shall automatically be the Head of the Community-Based SBP Monitoring Team and shall be responsible in inviting the PTA representatives, the School Boy Scout and Girl Scout Coordinator, and local Non-Government Organization.
 - ii. PTA Representatives. At least one (1) representative from the PTA shall be a member of the team.
 - iii. School Boy Scout and Girl Scout Coordinators They shall be automatically members of the team with the

- condition that they shall report to their local councils about the activities of the team.
- Local NGOs. Representatives from local NGOs shall be invited to be part of the team.
- v. Project Engineer. The project engineer, either from DepED (for Red and Black SBP) or from DPWH (for RSBP) depending on the implementing agency, shall automatically serve as the technical expert of the team.
- vi. Division Physical Facilities Coordinator (DPFC). The Division Physical Facilities Coordinator shall be automatically part of the team to represent the Division Office and shall further be the initial coordinator of the team before the election of the SBP Monitoring Community-Based SBP Monitoring Coordinator.
- 2. The SBP Monitoring Team members are to list themselves with the appropriate DepED school, district, division and regional offices to qualify themselves as official monitors of the project.
- 3. Members must not have any pecuniary interest in the contract as subcontractor, supplier, forwarder/transporter, or losing bidder/s.
- 4. Members of the team should not belong to the immediate family or related up to the third degree of consanguinity to the contractor, subcontractor, supplier, forwarder/transporter, or losing bidder/s. They should not be associated to the contractor, subcontractor, supplier, forwarder/transporter, or losing bidder/s.

E. Organization and Coordination of the Community-Based SBP Monitoring Team

- The Division PFC and the recipient School Principals of the RSBP and Red and Black SBP shall set a meeting with the members of the Community-Based SBP Monitoring team 2 weeks prior the procurement of the project to set the plans of the team and assign specific duties to accomplish the joint monitoring.
- The SBP Monitoring Team Coordinator shall be assigned by the team through a consensus. The SBP Monitoring Team Coordinator shall be the focal person that shall oversee the implementation of the plans as set by the team.
- 3. Regular meetings shall be set as deemed necessary/needed by the team.

F. Stages of the School Building Program Where School Community Participation Shall Be Institutionalized

- Site Identification and Pre-Engineering Surveys. The SBP Monitoring Team through the School Principal shall be consulted in the identification of the proper site for the school building construction for both RSBP and Red and Black Schools.
- Preparation of Program of Works (POW). The SBP Monitoring Team through the School Principal shall review and endorse the Program of Works once deemed most appropriate for the school. The School Principal shall further be one of the signatories of the POW for Red and Black Schools.
- 3. Procurement. The SBP Monitoring Team shall be invited as observer to the procurement process for both the RSBP and Red and Black Schools.
- 4. Construction Stage. During contract implementation, the team shall visit and inspect the school building construction site as often as deemed necessary to sufficiently answer the monitoring tool referred to in Annex B of this Memorandum.
- 5. Joint Final Inspection. The SBP Monitoring Team shall be part of the Joint Final Inspection of the school building, and the School Principal shall sign as one of the signatories in the Punch List Form (refer to Annex B).

G. Training of the SBP Monitoring Team

- This policy shall be introduced to the stakeholders to be spearheaded by the Division Physical Facilities Coordinators (DPFC) to be assisted by the DepED Project Engineers immediately following promulgation of this DepEd Memorandum.
- 2. The Division PFC shall however be in charge of orienting the school heads during the first SBP Monitoring Team Meeting, using the Bayanihang Eskwela Manual, a G-Watch initiated, joint public-private monitoring of School Building Projects which will include the following:
 - a. Roles of the SBP Monitoring Team
 - b. Overview of the DepED School Building Program
 - c. Standard processes and designs for school building projects.

H. Monitoring Tool

The monitoring shall be conducted using tested monitoring tools included in the Bayanihang Eskwela Manual.

I. Reporting Procedures

1. Regular reporting shall follow the process below:



- a. The Community-Based SBP Monitoring Team shall forward all their accomplished Bayanihang Eskwela Monitoring Tool (refer to Annex C and Annex D) to the Division Office 2 weeks after signing the Certificate of Completion of the school building project.
- b. The Division Offices shall then submit all reports from the schools to the Physical Facilities and Schools Engineering Division (PFSED) of the Department of Education not later than 2 weeks after the receipt of the accomplished monitoring tool.
- c. The PFSED shall consolidate all reports and address the findings every quarter.
- d. The PFSED shall make available to the public and other NGOs all monitoring tools and consolidated reports.
- 2. For reports requiring immediate feedback, the Community-Based SBP Monitoring Teams shall contact the implementing agencies through the following hotlines:

a. DPWH: 2920b. DepED: 2622

- 3. In cases where the implementing agencies do not respond, the teams may contact the following stakeholders:
 - a. Ombudsman
 - b. Bayanihang Eskwela Team (Government Watch):

Tel.

426-6001 local 4644

Telefax:

920-2920

Email:

government_watch@yahoo.com

- 4. Annual reports on the community-based monitoring of the school building projects shall be prepared by the PFSED.
- 5. The results of the Community Based SBP Monitoring shall also be presented regularly during the Annual Convention with the Physical Facilities Coordinators, DepEd Project Engineers/Architects and during the annual National DepED-DPWH Coordination Meetings to generate feedback and recommendations from all the stakeholders.

J. Responsibilities of DepED and DPWH Officials

- The Division Offices through the Division Physical Facilities Coordinator shall mobilize and invite volunteers for the SBP Monitoring Team as comprised in Part E of this Memorandum.
- The DPWH District Engineering Office through the District Engineer (for RSBP) and the DepED Division Offices, through the Division Physical Facilities Coordinator (for Red & Black SBP), has the responsibility of providing the SBP Monitoring Team all

pertinent documents which may include but not limited to the following:

- a. Procurement Schedule
- b. Bidding Documents
- c. Program of Works
- d. Implementation Schedule
- e. Accomplishment Reports
- f. Others
- 3. The Division Office, through the Division PFC, has the responsibility of inviting the SBP Monitoring Team to important meetings relevant to the school building project to be implemented. It shall also keep a database of SBP Monitoring Teams for each school building project it shall implement.
- The Division Office through the Division PFC, shall conduct an orientation with the SBP Monitoring Teams to train them on their roles in the school building project to be implemented.
- The Division Offices through the Division PFC, shall collect all monitoring tools and reports and submit these to the Physical Facilities and Schools' Engineering Division (PFSED) of the Department.
- 6. The PFSED shall consolidate all reports and make these available to the public and Non-Government Organizations (NGOs) that shall request for the reports.
- 7. The PFSED shall prepare an annual report on the community-based monitoring of the school building projects which it shall make available to the public and other Non-Government Organizations (NGOs).
- 8. The PFSED shall discuss the results of the community-based SBP monitoring with stakeholders to generate feedback from the School Principals, DepED Project Engineers, DPWH Project Engineers and the Division Physical Facilities Coordinators.

K. Responsibilities of the Community-Based SBP Monitoring Team

- 1. The team members shall lay down their plan of action in their first meeting and schedule the activities accordingly.
- 2. They shall conduct regular meetings as deemed necessary to accomplish the monitoring plan.
- The team shall join the inspection team of DepED and DPWH in monitoring the progress of school building project implementation, including the assessment of quality.

- 4. The team shall conduct unannounced inspections of the school building construction.
- The team shall jointly answer the monitoring tool prescribed in Annex C and Annex D and submit it to the Schools Division Superintendent through the Division Physical Facilities Coordinator.
- 6. The team shall further jointly or separately prepare a report indicating their observations on the SBP implementation.

L. Commendation and Incentives

- 1. Corresponding points shall be credited to Teachers and School Principals who have been active in the monitoring through the incentive program of DepED.
- 2. Failure on the part of concerned government officials to comply herewith shall be subject to corresponding administrative sanctions.